


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.  
A.H.Meyer No. 10.

SEC.30 T.18 R.7W  
SE NE SW  
990'S 330'W of Center

County. Rice

Total Depth. 3216'  
Comm. 8-16-41 Comp. 9-2-41  
Shot or Treated.  
Contractor. L.W.Prunty Drlg.Co., Inc.  
Issued. 11-15-41 Rotary O-3207  
Cable 3207-16



CASING:  
10 $\frac{3}{4}$ " 204' Cem.  
6" 3205' Cem.

Elevation.

Production. Pot.129.66 BO,  
no wtr,Phy.

Figures Indicate Bottom of Formations.

surface clay	30
shale & shells	185
shale	210
shale & shells	477
shale	825
shale & shells	1010
lime brkn	1108
lime	1229
lime brkn	1715
shale & shells	2116
lime brkn	2426
lime	2528
lime brkn	2628
lime	2665
shale	2742
limo brkn	2785
lime	3157
sand	3162
shale & shells	3183
sand	3190
lime	3195
shale	3205
dolomite	3208
limo	3217
Total Depth Corr.	3216

Top of Arbuckle lime 3204  
Total fillup w/oil 1600'  
9-3-41 acidized w/4000 Gals.  
9-5-41 on physical potential  
test the well pmpd 43.22  
BO in 8 hrs, giving the  
well a 24-hr potential of  
129.66 B.O., no wtr

Note: All of above footages  
are calculated from the  
cement floor level.