

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
A.H. Meyer No. 11.

SEC. 30 T. 18 R. 7W
NW SE SW
990' N 990' W of S $\frac{1}{4}$ Cor.

County. Rice

Total Depth. 3209'

Comm. 9-1-41 Comp. 9-16-41

Shot or Treated.

Contractor. L.W. Prunty Drlg. Co., Inc.

Issued. 11-15-41 Rotary O-3204
Cable 3204-09

CASING:

10 $\frac{3}{4}$ " 201' Cem.
6" 3202' Cem.

Elevation.

Production. Pot. 3000 B. Max.

Figures Indicate Bottom of Formations. Allowed Echo., No wtr,
(Ind. Cap. 4334 BO, Nowtr)

surface clay	15
shale & shells	163
shale & lime shells	208
shale	408
shale & shells	781
shale	1010
lime brkn	1504
shale & shells	1828
lime brkn	2236
lime	2655
shale	2710
shale & shells	2800
lime	2875
lime sft	2905
lime	3100
lime brkn	3151
shale & shells	3183
shale sft	3189
shale	3202
ddomite	3210
Total depth corrected	3209

Top of Arbuckle lime 3201

Total fillup w/oil 3175' -
swbd 136 BO in 3 hrs
9-18-41 acidized w/1000 Gals.
9-19-41 obtained a maximum
allowed potential by Echo.
of 3000 Bbls. Oil, no wtr -
indicated capacity 4334 B O,
No wtr

Note: All of above footages
are calculated from the
cement floor level.