


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
C.W. Poland No. 5.

SEC. 30 T. 18 R. 7W
SE NW SE
990' S & E of Center

Total Depth. 3175' (Cem. Floor level 3174)
Comm. 2-7-41 Comp. 2-24-41
Shot or Treated.
Contractor. L.W. Prunty Drlg. Co., Inc.
Issued. 4-19-41

County. Rice



CASING:
9 5/8" 202' Cem.
6" 3158' Cem.

Elevation. 1677

Production. Pot. 391 B.
No wtr

Figures Indicate Bottom of Formations.

surface clay, shale & shells	210
shale & shells	1045
lime brkn	1180
lime	1207
shale	1297
lime brkn	1833
shale & shells	2048
lime brkn	2456
lime	2625
lime brkn	2712
lime	2750
lime sft	2765
lime	2774
lime hrd	2842
lime sft	2875
lime brkn	2935
lime sft	2945
lime brkn	2950
lime	2990
lime hrd	3055
lime brkn	3100
shale	3157
dolomite	3175
Total Depth.	

3156
1677
- 1479

Total depth from cement floor level 3174

Top of Arbuckle lime from cement floor level 3156

2-23-41 T.D. 3167 in Arbuckle lime - acidized w/1000 Gals.
2-24-41 T.D. in Arbuckle lime - swbd 7 BO in 4 hrs off btm
2-25-41 acidized w/3000 Gals.
2-26-41 on physical potential test the well pumped 130.38 BO in 8 hrs, giving the well a 24-hr potential of 391 BO, no wtr

Arbuckle lime 3156-3174