

13-18-8W Platted  
J. R. Shook


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY:  
Union National Bk Bldg, Wichita, Kansas.

CONTINENTAL OIL CO:  
P. Nickel No. 1.

SEC 13 T. 18 R. 8W.  
NE SW SW  
990' N 990' E of SW COR 13 1936

County. Rice.

Total Depth. 3216.  
Comm. 2-2-36 Comp. 4-13-36.  
Shot or Treated. 2000 gal.  
Contractor.  
Issued. 6-13-36.



Elevation.

Production. Pot. 1428 B.

CASING:

13" 165' 8" 1367'  
5" 3210'

Figures Indicate Bottom of Formations.

shale and shells	125
sand and shale	166
shale and shells	680
salt	890
shale and shells	1345
broken lime and shale	1470
lime	1480
broken lime	1670
lime	1720
broken lime	1790
shale and shells	2040
lime	2045
shale	2100
shale and shells	2200
broken lime	2270
shale and shells	2425
lime	2485
broken lime	2745
lime	2765
broken lime	2850
lime	3090
shale and lime	3165
cored	3168
shale	3170
shaly shale	3191
shale	3209
lime	3216 Total Depth.

GEOLOGICAL TOPS:

Top Topeka 2385  
Top Kansas City 2785  
Top Simpson 3165  
Top Siliceous 3210

2500' oil in 2 hours at 3214 after drilling plug.  
Swab 600 bbls 15 hours 3-16-36.  
Swab 75 bbls 2 hours at 3216 3-17-36.  
Pump 825 bbls 18 hours 3-21-36.  
Pump 1428 bbls 24 hours 4-13-36

