


13-18-8W FLOTTED  
P.E.-J

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.  
P. Nickel No. 6

SEC. 13 T. 18 R. 8W.  
SE NE SW  
990'S 330' W of Cen of  
SEC.  
County Rice.

Total Depth. 3232.  
Comm. 3-17-38 Comp. 4-11-38  
Shot or Treated.  
Contractor.  
Issued. 7-2-38



CASING.

JUL 2 1938

103/4" 223' 7" 3227'6

Elevation.

Production. Pot. 1130 B. .  
no wtr.

Figures Indicate Bottom of Formations.

soil and sand	40	4-6-38	On initial potential test the well pumped
shale and sand	223	249.83	bbls oil the 1st 4 hours and 186.12 bbls oil
shale	310		the last four hours of the test, giving the well a
shale and red rock	785	24	hour Potential of 1116.72 bbls of oil no wtr
salt	980		
shale	1040	5-16-38	On state Potential test the well pumped
lime broken	1150	210.43	bbls oil the 1st four hours and 188.33 bbls
broken lime	1370		oil the last four hours giving the well a 24 hr
sdv lime	1405		potential of 1130 bbls oil no water.
lime	1435		Increase over previous potential of 13 bbls oil.
lime and shale	1540		
broken lime	1830		
shale and shells	1975		
shale and shells	2110		
lime	2155		
broken lime	2255		
shale and shells	2310		
broken lime	2360		
lime	2565		
broken lime	2575		
lime	2670		
shale and shells	2720		
lime	2750		
shale	2815		
broken lime	2825		
lime	3005		
broken sh oil	3015		
lime	3155	Top Arbuckle lime	3227
shale and shells	3190		
shale and sand	3210		
broken lime	3232		
Total Depth.			

The well was not acidized.