

13-18-8W

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - SHELL OIL CO.
Farm - E. Zajic No. 1-W

SEC. 13 T. 18 R. 8W
NE SW NE

Total Depth. 3784' SLM
Comm. 1-30-47 Comp. 3-16-47
Shot or Treated.
Contractor.
Issued. 4-26-47

County. Rice

KANSAS



Elevation. _____

Production. S.W.D.W.

CASING:

10 3/4" 257'
4 1/2" 3277'

Figures Indicate Bottom of Formations.

surface	65
sand	110
shale & shells	885
shale shells & salt	1040
lime brkn & shale	1195
shale & shells	1360
anhydrite & shale	1410
shale & lime	1540
lime	1600
shale & shells	1675
lime & shale	2405
lime	2665=2661 SL Corr.
lime	2800
shale & lime	2895
lime	2950
lime brkn	2998
lime & shale	3146
Conglomerate	3186
shale	3194=3188 SL Corr.
shale	3192
Dolomite	3784 SLM
Total Depth	

Tops:	
Topeka	2442
Lansing-Kans. City	2802-3146
Conglomerate Sooy	3146-3186
Simpson Shale	3186-3192
Arbuckle	3192-3784

Fair Oil stain	2997-3004
Poor Oil stain	3151-3153
No Oil stain	3186-3192
Fair Oil stain	3192-3250