

KANSAS WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
 Union National Bank Bldg, Wichita, Kansas.


YINGLING BROTHERS
 Maupin No. 1

Sec. 1 T. 18 R. 8 W.
 NW SW SW

Total Depth 3354
 Comm. 7-31-34 Comp. 2-9-35.
 Shot or Treated.
 Contractor S. A. Murphy.
 Issued 3-9-35.

County - Rice.

CASING



15 1/2" 256' 4" 6 5/8" 3020
 12 3/4" 1150 5 3/16" 3240 UR to 3260
 10" 2060 2 1/2" 3239
 8 1/2" 2775 U.R. 2850 5/8" 3239

Elevation 1750

Production Dry

Sec. 1
 K.C. 2850
 Cong 3210
 Sil 3240

Figures Indicate Bottom of Formations.

surface clay	85	red lime shells	1645	show oil	2876-2896
sand	95	shale blue	1670	lime drk	2900
7 BW 85-95		shale blue		lime grey	2905
sdv shale	105	hole caving	1700	lime drk	2910
shale blue	115	red rock hole		shale & brkn lime	2920
red rock 7 BW	140	caving	1720	lime HFV	2960
shale blue	200	shale blue hole		water sand	2970
sdv shale 2 BW	210	caving	1740	lime	2990
shale blue	235	Fighting cave		lime sdv	3000
sdv shale 3 BW	245	slate blue	1750	shale	3005
slate blue	250	lime	1770	sand	3010
shale blue	295	shale black	1775	lime	3020
red rock	340	lime brkn	1795	lime	3050
lime	355	slate white	1800	shale	3055
red rock	415	lime	1825	lime	3115
slate blue	430	slate blue	1830	shale drk	3123
red rock	580	lime	1870	lime white	3128
slate blue	660	lime shells shale	1890	shale lgt	3140
red rock	670	shale blue	1930	lime	3160
shelly red	690	lime	1940	Various color shale	3174
shale blue	765	shale blue	1970	shale drk	3195
lime shells	780	red rock	1975	shale hole caving	3200
shale blue	790	shale blue	2000	chat Viola	3210
salt	805	lime	2005	red rock	3215
salt brkn	885	slate blue	2020	red various colors	3223
salt brkn	940	lime	2035	lime shells	3226
slate blue	950	red rock		oil in sand	3233
salt brkn	1000	hole caving	2035	conglomerated & sand	
salt	1030	water sand 5 BW	2045	50 bbls oil show	
red rock	1040	shale	2060	drilling 1 & 2 foot	
slate blue	1080	slate blue	2110	testing out oil sand	3240
lime brkn	1100	slate blue	2120	lime	3243
shale brown	1120	lime	2160	shale showing	3245
lime grey	1130	shale	2165	Plugged back from	3245-3259
slate blue	1145	shale blue	2175	Testing Well	
lime grey	1170	lime	2185	lime sft	3253
slate white	1180	shale blue hole		lime hrd	3255
lime	1190	caving	2250	lime	3260
slate white	1225	lime	2255	red brkn shale	3262
lime	1250	slate blue	2370	lime	3263
slate white	1255	lime	2400	lime shells	3265
lime brkn	1275	slate blue	2430	various color shale with	
lime	1285	lime Topeka	2490	lime shells & sand	3267
lime brkn	1290	shale	2495	various color shale	3280
lime	1310	lime	2550	lime shells hole caving	
slate white	1325	slate blue	2570		3292
red rock	1335	lime	2615	various color shale	
lime 2 BW 1480	1500	fishing for bit		hole caving	3308
slate blue	1510	lime	2620	varigated	3335
lime	1520	lime	2695	shale blue	3347
red rock	1525	slate	2740	Silicious HFV	3354
lime	1550	slate	2765		
shale black	1560	lime Lansing	2775	Total Depth	3354
lime	1570	HFV 2775			
shale & red	1580	hole caving			
lime	1585	lime	2780		
shale brkn	1595	slate	2830		
shale pink	1615	shale	2835		
lime	1620	slate	2850		
shale	1625	lime	2896		

2765
 1750
 -1015Ls
 3340
 1750
 -1590Lb.

Sec. 1 - K.C. Lime 2850
 Sil. 3040

2850
 1750
 1101