


CONTINENTAL OIL CO.  
 F. E. Fuller No. 1.

SEC. 12 T. 18 R. 8W  
 SEC NW

DEEPENING RECORD

Total Depth. 3965'  
 Comm. 4-16-37 Comp. 5-11-37  
 Shot or Treated.  
 Contractor.  
 Issued. 6-6-42

County. Rice



CASING:  
 15" 197'  
 7" 3244'

Elevation. 1733

Production. Dry

Figures Indicate Bottom of Formations.

3244  
 1733  
 -1511

soil sand & shale	160	lime wh	3470
shale	195	lime gy	3604
shale & shells	785	lime gy hd	3612
salt	950	lime gy	3675
shale & shells	1100	lime lgt	3685
brkn lime	1333	lime wh	3695
brkn lime & sand	1410	lime lgt	3700
shale & shells	1530	lime wh	3724
lime	1565	lime brown	3754
shale	1610	lime gy	3763
shale & shells	2025	lime brown	3795
shale	2120	sand gy	3834
brkn lime	2330	sand brown hd	3840
lime	2355	lime hd	3845
brkn lime	2415	red rock	3850
lime	2600	lime sdy	3854
brkn lime	2610	lime sdy	3926
lime	2681	sand red	3935
shale	2702	sand	3959
brkn lime	2762	sand red	3965
lime	2815	Total Depth.	
shale	2825		
lime	2872		
shale	2880		
lime	2900		
shale & shells	2924		
lime	2958		
brkn lime	2968		
lime	3020		
brkn lime	3044		
lime	3120		
shale	3130		
brkn lime	3160		
chert	3163		
brkn lime	3180		
conglomerate	3227		
shale	3250		
lime	3254		
Total Depth.			

Ran 8 Jts. 182' of 5 1/2" osg  
 for liner. Top of liner  
 3210' btm of liner set @  
 3390-Cemented

After drlg to a T.D. of 3254  
 the hole had filled up  
 2600' w/wtr, 7 sacks of  
 cement was then dumped &  
 well was left standing.  
 4-20-38 work was started  
 on the well to drill deeper  
 for a salt wtr input well  
 5-31-38 on a 38-minute wtr  
 test the well took 409 BW  
 A liner was then set & cem.  
 w/20 sacks cement, the cem.  
 was then drld on a second  
 wtr test the well took 413  
 BW in 46 minutes.

3248-3252 Hole filled 1500' with  
 water - trace oil.  
 3252-3254 Hole filled 2600' with  
 water.

Top Siliceous lime 3244.

DEEPENING RECORD:

Comm. 4-20-38 Comp. 6-9-38

Input Well	
lime (cemented back)	3250-3254
lime blue	3250-3270
lime	3279
lime gy	3303
lime sdy	3308
lime	3327
lime brown	3365
lime gy	3442