

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
A. H. Johnson No. 5.

SEC. 12 T.18 R.8W
NE SW SW
990' N 990' E SW Cor.

Total Depth. 3236'
Comm. 4-27-40 Comp. 5-9-40
Shot or Treated.
Contractor.
Issued. 8-10-40

County. Rice



CASING:
10 $\frac{3}{4}$ " 203'
7 " 3195'

Elevation.

Production. Pot. 1047 B.

Figures Indicate Bottom of Formations.

surface clay	15
shale & lime shells	206
shale & shells	830
salt	1096
shale & shells	1490
lime brkn	1759
lime	1775
shale & shells	2156
lime brkn	2335
shale & lime brkn	2407
shale	2423
lime	2509
lime brkn	2519
shale & lime	2569
shale	2575
lime brkn	2740
shale & shells	2820
lime brkn	2928
lime	3157
shale & shells	3187
shale & lime	3194
Arbuckle dolomite	3236
Total Depth.	

Top Arbuckle 3194
2500' oil
Acidized w/2000 Gals. Acid
Swabbed 259 BO - 9 hrs
Acidized w/3000 Gals. Acid
Pumped 349 BO - 8 hrs
Potential 1047 B. 24 hrs.