


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

CONTINENTAL OIL CO.
A. H. Johnson No. 2.

SEC. 12 T. 18 R. 8W
SEc SW
330' N 330' W S/4 Cor.

Total Depth. 3240'
Comm. 2-1-38 Comp. 3-2-38
Shot or Treated. 2000 Gals.
Contractor.
Issued. 5-28-38

County. Rice



CASING:

10 $\frac{3}{4}$ " 225'
7" 3160'

Elevation.

Production. Pot. 2837 B.

Figures Indicate Bottom of Formations.

cellar	8
surface soil & shale	100
sand & shale	225
shale & shells	775
salt	980
shale & shells	1085
shale & lime	1265
brkn lime	1380
sand	1405
brkn lime	1845
shale & shells	2135
lime	2155
shale	2253
brkn lime	2360
lime	2665
shale	2685
shale & shells	2792
lime	3110
brkn lime	3143
sand	3150
conglomerate	3158
shale green	3161
Top Siliceous lime	3159
Siliceous lime	3240
Total Depth.	

Pumped 483 B. 1st 4 hrs.
Pumped 472 B. 2nd 4 hrs.
Pumped 2837 B. 24 hr Pot.