


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.  
P. Nickel No. 6

SEC. 13 T. 18 R. 0W.  
SE NE SW  
990'S 330' W of Cen of  
SEC.

County Rice.

Total Depth. 3232.  
Comm. 3-17-38 Comp. 4-11-38  
Shot or Treated.  
Contractor.  
Issued. 7-2-38



CASING.

103/4" 223' 7" 3227'6

Elevation.

Production. Pot. 1130 B. .  
no wtr.

Figures Indicate Bottom of Formations.

soil and sand	40	4-6-38 On initial potential test the well pumped
shale and sand	223	249.83 bbls oil the 1st 4 hours and 186.12 bbls oil
shale	310	the last four hours of the test, giving the well a
shale and red rock	785	24 hour potential of 1116.72 bbls of oil no wtr
salt	980	
shale	1040	5-16-38 On state Potential test the well pumped
lime broken	1150	210.43 bbls oil the 1st four hours and 188.33 bbls
broken lime	1370	oil the last four hours giving the well a 24 hr
sdv lime	1405	potential of 1130 bbls oil no water.
lime	1435	Increase over previous potential of 13 bbls oil.
lime and shale	1540	
broken lime	1830	
shale and shells	1975	
shale and shells	2110	
lime	2155	
broken lime	2255	
shale and shells	2310	
broken lime	2360	
lime	2565	
broken lime	2575	
lime	2670	
shale and shells	2720	
lime	2750	
shale	2815	
broken lime	2825	
lime	3005	
broken sh oil	3015	
lime	3155	Top Arbuckle lime 3227
shale and shells	3190	
shale and sand	3210	
broken lime	3232	
Total Depth.		

The well was not acidized.