


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
W.S. Pickerill No. 4

SEC. 13 T. 18 R. 8W.
NW 1/4 SE
330' S and 330' E of Center.

Total Depth. 3214
Comm. 11-13-38 Comp. 12-4-38
Shot or Treated. 2000 gal acid.
Contractor.
Issued. 1-28-39

County Rice.



CASING.

103/4" 227

7" 3211'

Elevation.

Production. Pot. 2347.44 B.

Figures Indicate Bottom of Formations.

shale and shells	790
salt limc and shale	1160
shale and limc	1325
shale and limc	1545
shale and shells	2355
limc	2460
broken limc	2560
limc	2645
limc	2680
shale	2750
limc	2820
limc	2865
limc	3160
shale	3208 Top Arbucklo limc 3210
sand	3209
shale	3212
arbucklo limc	3214
Total Depth.	

The cement plug was drilled and hole filled up 300' in 30 min. The well was drilled to a total depth of 3214 and filled up 2800' with oil. No pumping test on well before acidizing.

12-6-38 The well was acidized with 2000 gal acid.

12-7-38 On initial potential test the well pumped 782.48 bbls of oil in 8 hours., giving the well a 24 hour potential of 2347.44 barrels of oil no water.