


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL Co.  
J.A. Williams. No. 3.

SEC. 13 T. 13 R. 3W.  
NE SE NW  
330' W. 990' N of Center of Sec.

Total Depth. 3223.  
Comm. 3-31-33 Comp. 9-17-33  
Shot or Treated. 3000 gal.  
Contractor.  
Issued. 11-5-33

County Rice.



CASING.

103/4" 215' 7" 3195

Elevation.

Production. Pot. 2489 B.  
No wtr

Figures Indicate Bottom of Formations.

collar	9
soil sand and shale	215
shale and red rock	585
red rock and shale	750
salt	1000
shale and shells	1150
broken lime	1235
broken lime	1360
sdv lime	1420
broken lime	1590
shale and shells	2117
broken lime	2146
shale and shells	2370
lime	2545
broken lime	2640
lime	2680
shale and shells	2800
lime	3155
shale and sand	3192
shale	3198
arbucklo lime	3199
lime	3223

Top of Arbucklo line 3194

The cement plug was drilled and the hole filled up with oil in 1 1/2 hrs.

Well was acidized with 3000 gal acid.

Total Depth.