


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

SHELL PETRO. CORP.
E. Zajko No. 1

SEC. 13 T. 18 R. 8W.
NW NW NE
330' NL 330' WL NE $\frac{1}{4}$

Total Depth. 3242
Comm. 12-6-37 Comp. 1-3-38
Shot or Treated.
Contractor.
Issued. 1-29-38

County Rice.



CASING.

13" 242'
7" 3159'

Elevation.

Production. Pot. 2331 B.
No wtr.

Figures Indicate Bottom of Formations.

sand	41	dolomite few porous strks well
red bed and shells	245	oil stained 3230
shale	250	dolomite small amount porosity
iron	270	and oil staining 3235
anhydrite and lime	305	dolomite poor porosity small
red bed and shells	460	amount oil staining 3240
red bed and shale	540	dolomite fair porosity and
shale and shells	810	oil staining 3242
salt	1010	Total Depth.
shale	1040	3100 oil at 3242.
shale and lime	1506	
lime	1570	
lime and shale	1620	
lime and shale	1884	
lime and shale	2070	
shale and lime shells	2100	
lime	2134	
lime and shale	2405	
lime	2744	
shale and lime	2795	
lime	2800	
lime	2965	
lime	3046	
3046 equals 3042 SLC (df)		
lime	3107	
lime and shale	3145	
shale lime and sand	3161	
dolomite	3162	
dolomite, pale green shale	3167	
3167 equals 3163 SLC		
dolomite	3165	
dolomite, green shale	3170	
dolomite	3174	
some oil from porous strks		
dolomite	3180	
dolomite green shale and		
white chert	3183	
dolomite small amount of		
oil	3184	
dolomite small amt oil		
stain	3187	
dolomite	3191	
dolomite green shale & chert	3195	
dolomite	3200	
dolomite fair porosity well		
oil stained	3205	
dolomite fair porosity		
fair oil stain	3210	
dolomite	3215	
small amount oil stain	3215	
dolomite poor porosity	3225	
small amt oil staining.		
3000' oil in hole.		