


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

SHELL PETROLEUM CORP.
E. Zajic No. 6

SEC. 13 T. 18 R. SW.
NW NE NE
330' NL 1045' EL. NE $\frac{1}{4}$

Total Depth. 3216.
Comm. 8-16-38 Comp. 9-2-38
Shot or Treated.
Contractor Campbell Drlg. Co.
Issued. 10-3-38

County. Rice.



CASING.

103/4" 251' 7" 3181'

Elevation.

Production. Pot. 2544 B.
no wtr.

Figures Indicate Bottom of Formations.

cellar	10
sand shale & shells	258
red bed shale and shells	560
shale and shells	700
salt	990
shale and shells	1030
anhydrite	1055
shale and lime streaks	1180
broken lime and shale	1505
broken lime	1560
shale	1570
shale and shells	1660
lime	1685
shale and lime shells	1720
broken lime and shale	1800
shale and shells	1935
shale and limestrks	2070
shale and lime shells	2145
shale and shells	2356
lime	2360
lime shale streaks	2377
lime	2565
lime and shale	2795
lime	3128
shale and sand	3132
conglomerate	3143
sand	3147
conglomerate	3155
sand	3159
cong. var. ool shale	3165
shale green	3178
dolomite	3180
3180-82 SLC	
dolomite	3216
Total Depth.	

Spotted Oil stain. 2802-05
good porosity Oil stain. 2855-62
no oil stain 2883-2903
Scattered Oil stain 2950-53
Small porosity and trace of stain. 2975-85
small amount porosity poorly oil stain 3147
fair porosity and spotted oil stain 3159
3150' oil 3195