


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk Bldg., Wichita, Kansas

SHELL PETRO.CORP.
 E.Zajic No. 9.

SEC. 13 T. 18 R. 8W
 NW SE NE
 999' fr SL 988' fr EL NE $\frac{1}{4}$

Total Depth. 3227'
 Comm. 9-26-38 Comp. 10-14-38
 Shot or Treated. 2000 Gals.
 Contractor. Campbell Drlg.Co.
 Issued. 11-12-38

County. Rice



CASING:
 10 $\frac{3}{4}$ " 250'
 7 " 3204'

Elevation.

Production. Pot. 2788 B.

Figures Indicate Bottom of Formations. No wtr.

shale & shells	253
red bed, shale & shells	773
salt & shale	868
shale & shells	1180
shale & limo strks	1472
brkn lime	1610
shale & lime strks	1760
shale & limo shells	1828
brkn lime	1960
shale & shells	2105
shale & lime shells	2207
shale & shells	2265
lime	2285
shale & shells	2312
brkn lime & shale	2461
lime	2655
shale & lime	2738
brkn lime & shale	2783
lime & shale	2845
lime	2988
trace oil stain	
brkn lime	3040
lime	3160
conglomerate	3161
sand	3164
light oil stain	
conglomerate	3189
fair por. & some stain	
shale green	3203
dolomite	3205
fair oil stain	
3209 equals 3205 SL Corr,	
dolomite	3227
Total Depth.	

1600' oil at 3208
 2900' oil at 3212
 3150' oil at 3225