

SHELL PETRO. CORP.
 E. Zajic No. 12.

SEC. 13 T. 18 R. 8W
 SE SW NE
 330' fr SL 987' fr WL NE 1/4

Total Depth. 3227'
 Comm. 11-6-38 Comp. 11-23-38
 Shot or Treated.
 Contractor. Campbell Drlg Co.
 Issued. 12-24-38

County. Rice



CASING:
 10 3/4" 210'
 7 " 3211'

Elevation.

Production. Pot. 2630 B.
 No wtr.

Figures Indicate Bottom of Formations.

shale, shells, sand	250	dolomite grey to wh, strks	
red bed	315	fair to good por & stain	3212
red bed, shale & shells	670	dolomite	3227
red bed & shale	700		
salt & shale	865	Total Depth.	
shale, shells, salt	947	2900' oil	3215
shale & salt	1015	Top Arbuckle Dol	3210
shale & lime shells	1195		
shale & lime strks	1330		
shale & lime shells	1515		
shale & lime strks	1645		
shale & shells	1920		
shale & lime shells	2005		
shale & lime strks	2067		
shale	2105		
lime	2138		
shale	2145		
shale & lime shells	2214		
brkn lime, shells, shale	2268		
shale	2288		
shale & lime strks	2365		
brkn lime	2411		
lime	2486		
shale	2498		
shale & lime	2503		
lime	2528		
brkn lime	2602		
lime	2656		
brkn lime & shale	2693		
shale	2718		
lime	2728		
brkn lime & shale	2773		
lime	3016		
good to fair por w/slight			
trace poor stain	2813-22		
strks fair por & fair oil			
stain	2872-78		
good porosity, no oil			
stain	2894-2915		
porosity w/few strks fair			
staining	2952-56		
fair to poor por., trace poor			
oil stain	2993-98		
lime	3110		
brkn lime	3154		
conglomerate, mostly shale			
grey to brown w/strks grey			
lime & intermixed chert in			
upper part	3188		
conglomerate shale as above			
w/strks sand having poor			
porosity & none to light			
oil stain	3189		
sand strks from	3185-87		
shale green med hrd	3193		
shale green w/intermixed			
pyrite, mostly pyrite in			
btm part	3206		
sand med sft, strks fair por.			
& oil stain	3210		