


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL Co.
J.A. Lewis No. 1.

SEC. 14 T. 18 R. 8W.
NEc NE
330' S 330' W of NE cor.

Total Depth. 3242.
Comm. 5-1-38 Comp. 5-18-38
Shot or Treated.
Contractor.
Issued. 7-30-38

County Rice.



CASING.

103/4" 200'
7" 3229'

Elevation.

Production. Pot. 1455.24B.

Figures Indicate Bottom of Formations.

surface	40	
sand and shale	200	
shale and red rock	640	
shale	850	
salt	1025	
shale and shells	1400	
sand	1425	
broken lime	1655	
shale and shells	2140	
broken lime	2165	
shale and shells	2380	
broken lime	2445	
lime	2645	
broken lime	2655	
lime	2690	
shale and shells	2775	
lime	2800	
broken lime	2826	
lime	3120	
broken lime	3180	
shale and sand	3208	
shale	3235	
Arbuckle lime	3240	Top of Arbuckle lime 3228'
lime	3242	

Total Depth.

On a 6 hour pumping test the well pumped 373.86 bbls oil, no water.
On initial potential test the well pumped 242.54 bbls oil the first
four hours and 245.22 bbls of oil the last four hours giving the well
a 24 hour potential of 1455.24 bbls of oil. No water. Nat. No acid used.