


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO (COMMUNITY)
B.B. Ainsworth No. 7.

SEC. 24 T. 18 R. 8W
SW NW SE
990' fr NL 330' fr WL SE $\frac{1}{4}$

Total Depth. 3187'
Comm. 3-2-41 Comp. 3-19-41
Shot or Treated. 2000 Gals. Acid
Contractor. Prunty Drlg. Co.
Issued. 4-5-41

County. Rice



CASING:
9 5/8" 196' Cem.
6" 3170' Cem.

Elevation.

Production. Pot. 2538 B. Echo.

Figures Indicate Bottom of Formations. Draw-down, No wtr

clay, shale & shells	100
shale & shells	565
shale	1010
lime brkn	1348
lime	1559
lime brkn	1609
shale & shells	1798
shale	2100
lime	2111
lime brkn	2361
lime	2655
shale	2720
lime	2860
lime sft	2880
lime brkn	2912
lime	3110
lime brkn	3122
shale	3170
dolomite	3175
3175=3174 SLM(DF)	
dolomite	3187
3025' oil in hole	
Total Depth.	

Swab 200 oil & 0 wtr 4 hrs
Acidized 2000 Gals.
Established State potential
of 2538 oil & 0 wtr by
Echometer draw-down test.

Top Arbuckle dolo. 3169