

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
W.S. Pickerill No. 3-A


SEC. 24 T. 18 R. 8W.
NE SE NE
990' N 330' W of E. quarter
corner.

Total Depth. 3180
Comm. 6-24-39 Comp. 7-11-39
Shot or treated. 3000 gal acid.
Contractor.
Issued. 8-26-39

County Rice.

CASING.

10 3/4" 223'
7" 3127'



Elevation.

Production. Pot. 2274 B.

Figures Indicate Bottom of Formations.

shale and shells	802	
shale	852	
salt	927	
shale and shells	1047	
broken lime	1485	
lime	1703	
broken lime	1781	
shale and shells	1965	
shale	2065	
shale and shells	2362	
limo	2577	
broken limo	2627	
shale	2665	
broken limo	2688	
shale and shells	2740	
limo	2800	
broken limo	2846	
limo soft	2876	
limo hard	2922	
limo soft	2930	
limo	3000	
broken limo	3112	
shale	3126	
Arbuckle dolomite	3180	show oil
Total Depth.		

Top Arbuckle lime 3126

When the plug was drilled the hole filled 1500' with oil in 1 hour.
Total fill up 3000'

Pumping test before acidizing, pumped 233 bbls of oil in 3 hours and pumped off.

July 14, 1939 acidized with 3000 gal acid.

On initial potential test the well pumped 758.12 bbls oil in 8 hours giving the well a 24 hour potential 2274 bbls oil no wtr.

Total depth from cement floor 3179

Arbuckle limo 3126-3179