


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
 412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.  
 W.S. Pickerill No. 4-A.

SEC. 24 T. 18 R. 8W  
 SEc NE  
 330'N & W E $\frac{1}{4}$  Cor.

County. Rice

Total Depth. 3174'  
 Comm. 9-15-39 Comp. 10-7-39  
 Shot or Treated. No acid used.  
 Contractor.  
 Issued. 12-23-39



CASING:

10 $\frac{3}{4}$ " 207'  
 7" 3088'

Elevation.

Production. Pot. 2113 B. Nat  
 No water

Figures Indicate Bottom of Formations.

shale & shells	145
sdv shale	212
shale	242
red rock	262
shale & shells	1027
lime brkn	1504
shale & shells	2257
lime	2611
shale	2645
shale & shells	2726
lime	2768
lime hrd	2806
soft	2813
hard	2824
soft	2854
lime	3060
shale	3081
sand	3084
shale	3088
Arbuckle dolomite,	
good sh oil	3091
shale & lime	3095
lime	3174
Total Depth.	

Total Depth from cement floor  
 level 3174

Top of Arbuckle lime from  
 cement floor level 3087

Hole filled full of oil

10-11-39 on initial potential

test well pumped 704.28 BO

8 hrs giving the well a 24-

hr potential of 2113 BO,

no wtr. Natural no acid used.