


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
W.S. Pickerill "A" No. 7

SEC. 24 T. 18 R. 8W.
SE SW NE
330' N and 990'E of Center

Total Depth. 3173
Comm. 8-12-40 Comp. 8-29-40
Shot or Treated.
Contractor.
Issued. 11-30-40

County Rice.



CASING.

10 3/4" 217'
7" 3159'

Elevation.

Production. Pot. 4894 B.
No wtr. Allowable
3000 bbls.

Figures Indicate Bottom of Formations.

surface clay and sand	38
shale and shells	225
shale	303
shale and shells	1214
broken lime & shale	1344
broken lime	1428
shale and shells	1585
broken lime	1912
shale and shells	2305
lime	2588
broken lime	2750
lime	3050
shale and shells	3140
sand and shale	3157
Arbuckle	3173
Total Depth.	

3172 - T.D. from cement floor level.

Top of Arbuckle lime from cement floor level 3156

Hole filled up 1600' with oil the first hour, when plug
was drilled. - total fill up 3100'

9-3-40 On initial potential test taken by Echo meter the well was
given a 24 hour Pot. of 4894 bbls of oil, no water. This
potential establishes a max allowed potential of 3000 B.