


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL COMPANY.  
W.S. Pickerill "A" No. 9

SEC. 24 T. 18 R. 8W.  
SW NE NE  
990' S 990' W. NE cor.

Total Depth. 3191 (Cement Floor level 3190)  
Comm. 1-21-41 Comp. 2-8-41  
Shot or Treated.  
Contractor. L.W. Prunty Drilling Co., Inc.  
Issued. 4-5-41

County. Rice.



CASING.

103/4" 204' Cemented.  
6" 3161' Cemented.

Elevation.

Production. Pot. 3000 B.

Figures Indicate Bottom of Formations. Echometer No water.

shale and shells	185
shale lime shells	210
shale and shells	1389
lime	1454
broken lime	1486
shale and shells	1597
broken lime	1733
shale and shells	2237
lime	2257
shale and shells	2286
broken lime	2387
lime	2417
broken lime	2651
shale and shells	2740
lime	3050
broken lime	3120
lime	3125
sand	3135
lime and shale	3159
shale	3160
Arbuckle lime	3166
lime and shale	3174
lime	3191
Total Depth.	

Total Depth from cement floor level 3190

Top of Arbuckle lime from cement floor level 3159

Total Fillup with oil 3050' Swabbed 250 bbls of oil in 5 hours.

2-10-41 Established an echometer Potential of 3000 bbls of oil no water