

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
W.S. Pickerill No. 1-A.

SEC. 24 T. 18 R. 8W.
NE NW NE
330' S 990' E of N $\frac{1}{4}$ cor

Total Depth. 3224
Comm. 4-30-38 Comp. 5-23-38
Shot or Treated.
Contractor.
Issued. 7-30-38

County Rice.



CASING.

103/4" 195'
7" 3193'

Elevation.

Production. Pot. 2138.76 B.

Figures Indicate Bottom of Formations.

shale and shells	750	
salt	1035	
shale and shells	1385	
sand	1408	
broken lime	1830	
shale and shells	2370	
lime	2670	
shale and shells	2800	
lime	3150	
shale and sand	3172	
sand	3175	
shale	3198	Top of Arbuckle lime 3192.
lime	3224	
Total Depth.		

Drilled plug to bottom at 3196 and the hole filled up 1400' with oil.
On a six hour pumping test the well pumped 512 bbls of oil.

On initial Pot. test the well pumped 363.14 bbls of oil the first four hours and 356.46 bbls oil the last four hours of the test giving the well a 24 hour Potential of 2138.76 bbls of oil. No water. Natural. No acid used.