


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. ISERN DRILLING COMPANY
Farm. Groth No. 1

SEC. 10 T. 18 R. 9W
NE NE SW

Total Depth. 3237'
Comm. 4-30-56 Comp. 5-7-56
Shot or Treated.
Contractor.
Issued. 7-28-56

County Rice KANSAS



CASING:
8 5/8" set at 224' cem. w/150 sacks
5 1/2" set at 3230' cem. w/100 sacks

Elevation. 1736' DF

Production. 31 BOPD

Figures indicate Bottom of Formations.

clay	63
sand rock	85
clay	135
sand rock	150
clay	166
blue shale	219
shale & shells	325
red bed	400
Anhydrite	430
shale & shells	860
salt	1025
shale & shells	1350
lime & shale	1494
sand	1527
lime & shale	1930
shale & shells	2460
lime & shale	2734
Heebner	2738
Lime & shale	2810
shale & shells	2853
lime	3065
lime & shale	3124
lime	3235 RTD
lime	3237

Total Depth

TOPS:

Heebner	2735
Lansing	2871
Simpson Shale	3222
Simpson Sand	3225

CABLE TOOL REPORT:

Moved in cable tools, rigged up, drilled float collar, cem. & shoe. Cleaned hole out to total rotary depth 3235'. Swabbed hole down. Drilled new hole 3235-3237. Well making 25 gal. fluid per hour. Frac with 3,000 gal. oil & 3,000 # sand. Swabbed 19.39 barrels in 8 hour test.

Cable Tools Commenced 5-9-56
" " Completed 5-16-56