


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- ISERN DRILLING COMPANY et al  
Farm- Groth No. 2

SEC. 10 T. 18 R. 9W  
SW SE NW

Total Depth. 3256  
Comm. 6-28-56 Comp. 7-25-56  
Shot or Treated.  
Contractor.  
Issued. 9-29-56

County Rice  
KANSAS



CASING:  
8 5/8" 218' cem w/150 sx.  
5 1/2" 3254' cem w/100 sx.

Elevation. 1725 D.F.

Production. Making approx. 9½  
BOPH, 20% water

Figures indicate Bottom of Formations.

shale	275
red rock	400
anhydrite	430
shale, shells	860
salt	1030
shale, shells	1345
lime, shale	1445
sand	1470
lime, shale	1887
shald, shells	2465
lime, shale	2655
Heebner	2726
lime, shale RTD	3255
Cable Tools	
lime	3256
Total Depth	

Tops: Scout	
Heebner	2725
Lansing	2870
Simpson	3210
Arbuckle	3252

Rigged up Cable tools.  
Drilled cement from 3232-3255.  
Drilled new hole 3255-56.  
Sw. w/35 sx cem. Drid Cmt.  
to 3253. Perf. w/8 shots  
3251-52. Sand-frac w/3000#  
sand & 3000 gals. acid. Set  
Baker bridge plug @ 3230'.  
Perf. w/8 shots 3213-18..Well  
making approx. 1½ boph nat.  
Sand-frac w/3000# sand & 3000  
gals. acid. Tested well.  
Making approx. 9½ BOPH, 20% wtr.