

30-19-1W Plotted
about 11/10/37

Plotted Texas CO.


PHILLIPS PETRO. CORP.* SHELL PETRO.
C.E. Garrett No. 5
DEEPENING RECORD.

SEC. 30 T. 19 R. 1W.
SE NE NE
990' NL 330' E.L.

Total Depth. 3538
Comm. 6-21-34 Comp. 7-31-34
Shot or Treated. 1000 gal acid.
Contractor. J.E. Mabce.
Issued. 3-20-37

County. McPherson.

MAR 20 1937



CASING.

133/8" 236' 85/8" 3410'
7" 3415'

Elevation.

Figures Indicate Bottom of Formations. 107 BW 3 day Pot. Test.

surface and soil	70
sand and shale	303
shale and shells	449
sand and shale	585
shale and shells	790
lime	850
shale and shells	943
shale	1077
shale and shells	1281
shale	1370
shale and shells	1435
shale and shells	1658
shale and shells	1846
shale and lime	1882
shale and shells	1946
lime	1987
broken lime and shale	2013
shale	2017
lime	2070
shale and shells	2260
broken lime	2297
lime	2496
lime	2573
shale	2602
lime	2641
broken lime	2670
lime	2773
lime	2810
broken lime	2840
lime	2863
lime	2873
broken lime	2908
sdv shale	2915
shale and shells	2935
shale	2939
chat	3006
chat and lime	3039
broken shale	3047
lime	3072
lime	3132
lime	3157
Missing	3235
shale	3260
shale and shells	3278
shale	3410
standardizing rig.	

shale 3415
lime 3419 T.D.
100' OIH 1 hour no water by bailing.
Pay 3415-19
Pump 36 oil and 22 wtr 17 hours.
8-4-34. Pump 157 bbls oil and 60 wtr
24 hours.
8-6-34. Pump 144 B.O. 55 BW 1st 24 Hr.
8-7-34. Pump 106 Oil and 145 BW 24 Hr.
8-8-34 Pump 105 Oil 120 wtr 24 Hr.
Average 118 bbls oil and 107 BW 3 day
pot. test.

DEEPENING RECORD.

Old T. D. 3419
Comm. 1-14-37
Comp. 2-6-37
Prod. Salt Wtr. disposal.
5 1/2" 3523
sdv lime 3432
limo 3451
limo & sand 3460
sand 3471
limo 3473
sdv limo 3478
shale 3479
limo 3494
sand 3502
shale green 3505
sdv shale 3507
sand 3532
lime 3538
P.B. 3525
lime 3538- 3549
broken limo 3551
lime 3552
3551 - 2900' wtr. level
650' from top.
Total Depth.