

30-19-1w
5 C.E. Garrett

PHILLIPS PETROLEUM COMPANY

Wichita
February

Phillips plugged #3 and
and Western Supply and
Tadua plugged #1 and 2
No record of what happened
to #5.

State Corporation Commission
800 Bitting Building
Wichita, Kansas

Gentlemen:

Replying to your letter of January 6, 1937 relative to completion information on C. E. Garrett #5 we submit the data required on order #36-01-23, Rules 324.51 paragraphs "C", "E", and "F" and Notice of Commencement.

"C" - Salt water is desired to be injected into Simpson (Wilcox sand) with a top depth of 3462' and a bottom depth of 3524' and also the Arbuckle Dolomite formation with a top depth of 3524' and a total depth of 3442'.

"E" - Log of Deepening

O. T. D. - 3419'

Viola Lime	-	3415 - 3442
Simpson Dol.	-	3442 - 3458
Simpson Shale	-	3458 - 3462
Simpson Sand	-	3462 - 3502
Shale	-	3502 - 3510
Sand & Shale	-	3510 - 3515
Shaley sand	-	3515 - 3520
Sand	-	3520 - 3524
Top Siliceous		3524
Sandy Dol.	-	3524 - 3530
Dolomite	-	3530 - 3552
Total Depth	-	3552

JUL 12 1935
State Geologist Bureau
WICHITA, KANSAS

"F" - Casing Record

Size	Length	Seat Depth	Condition	Cemented	Feet Incased In Cement	Sacks Cement Used
13 3/8	248	248	Good	Yes	All	200
8 1/4	3427	3404	"	"	"	400
5 3/16	3523	3523	"	"	318	50

RECEIVED
STATE CORPORATION COMMISSION


JUL 11 1935

CONSERVATION DIVISION
Wichita, Kansas

712

Total Depth. 3538
Comm. 6-21-34 Comp. 7-31-34
Shot or Treated. 1000 gal acid.
Contractor. J.E. Maboo.
Issued. 3-20-37

County. McPherson.



CASING.

133/8" 236' 85/8" 3410'
7" 3415'

Elevation.

Production. Average 118 B.O.

Figures Indicate Bottom of Formations. 107 BW 3 day Pot. Test.

surface and soil 70
sand and shale 303
shale and shells 449
sand and shale 585
shale and shells 790
lime 850
shale and shells 943
shale 1077
shale and shells 1281
shale 1370
shale and shells 1435
shale and shells 1658
shale and shells 1846
shale and lime 1882
shale and shells 1946
lime 1987
broken lime and shale 2013
shale 2017
lime 2070
shale and shells 2260
broken lime 2297
lime 2496
lime 2573
shale 2602
lime 2641
broken lime 2670
lime 2773
lime 2810
broken lime 2840
lime 2863
lime 2873
broken lime 2908
sdy shale 2915
shale and shells 2935
shale 2939
chat 3006
chat and lime 3039
broken shale 3047
lime 3072
lime 3132
lime 3157
Missing 3235
shale 3260
shale and shells 3278
shale 3410
standardizing air

shale 3415
lime 3419 T.D.
100' OIH 1 hour no water by bailing.
Pay 3415-19
Pump 36 oil and 22 wtr 17 hours.
8-4-34. Pump 157 bbls oil and 60 wtr
24 hours.
8-6-34. Pump 144 B.O. 55 BW 1st 24 Hr.
8-7-34. Pump 106 Oil and 145 BW 24 Hr.
8-8-34 Pump 105 Oil 120 wtr 24 Hr.
Average 118 bbls oil and 107 BW 3 day
pot. test.

DEEPENING RECORD.

Old T. D.
Comm. 1-14-37
Comp. 2-6-37
Prod. Salt Wtr. disposal.
5 1/2" 3523
sdy lime 3452
lime 3451
lime & sand 3460
sand 3471
lime 3473
sdy lime 3476
shale 3479
lime 3494
sand 3502
shale green 3505
sdy shale 3507
sand 3532
lime 3538

P.B. 3525
lime 3538- 3549
broken lime 3551
lime 3552
3551 - 2900' wtr. level
650' from top.
Total Depth.

RECEIVED
STATE CORPORATION COM.

3415 JUL 11 1985

CONSERVATION DIVISION
Wichita, Kansas

30-19-1w
PI

GARRETT REPRESSURE WELL #5

OIL OPERATORS AND SURFACE OWNERS

SW/4 Sec. 19-19S-1W, McPherson County, Kansas
Operator Homer Krehbiel Oil, 1343 N. Maple, McPherson, Kansas 67460
Surface East 80 ac., A. J. Koehn, RR, Galva, Kansas 67443
Surface West 80 ac., Rozella Jost, & M. G. Jost, 1st National Bank, Hillsboro, Kansas 67063

SE/4 Sec. 19-19S-1W, McPherson County, Kansas
Operator George Hess, Box 905, McPherson, Kansas 67460
Surface Clyde Wedel, Canton, Kansas 67428

W/2 SW/4 Sec. 20-19S-1W, McPherson County, Kansas
Operator None (Producers Oil has a SWD well on this property.)
Surface Robert Decker, Canton, Kansas 67428

N/2 NW/4 Sec. 29-19S-1W, McPherson County, Kansas
Operator None
Surface Robert Decker, Canton, Kansas 67428

S/2 NW/4 Sec. 29-19S-1W, McPherson County, Kansas
Operator None
Surface V. C. Horn, 1261 Harding, Wichita, Kansas 67220

NE/4 Sec. 30-19S-1W, McPherson County, Kansas
Operator None - Producers Oil Company, 711 Philtower Bldg, Tulsa, OK 74103, owner of salt water repressure well located on C NW/4 NE/4 for which this application is being submitted.
Surface Herb Krehbiel, Moundridge, Kansas 67107

NW/4 Sec. 30-19S-1W, McPherson County, Kansas
Operator Paul Bandy Oil Producers, Box 364, Canton, Kansas 67428
Operator Producers Oil Company, 711 Philtower Bldg, Tulsa, OK 74103 has lease on NW NW NW and SE SE NW.
Surface Ruth V. Anderson, 5269 Woodson, Mission, Kansas 66202

SE/4 Sec. 30-19S-1W, McPherson County, Kansas
Operator Producers Oil Company, 711 Philtower Bldg, Tulsa, OK 74103 has lease on NW NW SE, SW SW SE and SE SE SE
Surface Pat Lewis, Route 2, Canton, Kansas 67428

N/2 SW/4 Sec. 30-19S-1W, McPherson County, Kansas
Operator Hiebert and Wedel, 1136 Wheeler, McPherson, Kansas 67460
Surface Chester Schmidt, Route #1, Galva, Kansas 67443

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1985

CONSERVATION DIVISION
Wichita, Kansas