

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:		
Well No.	Lease Name			
S _____ T _____ R _____ E _____ W _____				
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				
Date Received	Signature Title Date			

30-19-1W

15-113-20387

30-19-1W

State Geological Survey
WICHITA, BRANCH**Blackstone Drilling, Inc.**

Box 455 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

October 12, 1976

COMPANY: HOMER G. KREHBIRL
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: LEWIS #1
 LOCATION: 863' WEL & 460' SNL, of SE/4 30-19-1W
 McPherson County, Kansas
 COMMENCED: October 6, 1976
 COMPLETED: October 11, 1976
 ELEVATION: 1572 K. B.

0	to	75	Clay & Sand
75	to	105	Shale
105	to	165	Blue Shale
165	to	617	Shale & Lime
617	to	885	Lime & Shale
885	to	1335	Shale
1335	to	1855	Shale & Lime
1855	to	2770	Lime
2770	to	2875	Lime & Shale
2875	to	2946	Shale
2946	to	2972	Mississippi
		2972	T. D.

MAR 17 1976

Cut 12 $\frac{1}{4}$ " hole to 155' and ran 157' of 8 5/8" pipe, cemented with 100 sacks of cement at 155'. Plug down at 9:30 A. M., October 6, 1976. Cut 7 7/8" hole to 2972'. Run 2978' of 5 $\frac{1}{4}$ " pipe, set at 2970' with 60 sacks of cement 2 feet off bottom. Plug down at 9:15 P. M., October 11, 1976.

TOPS: LANSING - 2338' MISSISSIPPI - 2946'

Measurements taken from K. B.

CERTIFICATE

I, Charles D. Johnson, Secretary Treasurer of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Lewis #1, located on the 863' WEL & 460' SNL of SE/4, Section 30-19-1W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.


 Charles D. Johnson, Secretary-Treasurer