

32-19-1W
SW NW NW

Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

March 17, 1980

COMPANY: HOMER G. KREMBIEL, SR.
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: BLAIR #1
LOCATION: 1113' SNL & 305' EWL NW/4 Section 32-29-1W,
McPherson County, Kansas
COMMENCED: March 7, 1980
COMPLETED: March 15, 1980
ELEVATION:

0	to	50	Clay & Shale
50	to	125	Sand & Shale
125	to	165	Shale
165	to	627	Shale & Lime
627	to	900	Lime & Shale
900	to	2503	Shale & Lime
2503	to	2920	Lime
2920	to	2934	Lime & Shale
2934	to	3011	Mississippi
		3011	T. D.

Cut 12 1/2" hole to 158' and run 160' of 8 5/8" surface casing, cemented with 100 sacks of cement at 158'. Plug down at 12:15 P. M., March 7, 1980. Drilled a 7 7/8" hole to 3011'. Run 3018' of 5 1/2" casing, cemented 1 foot off bottom at 3010' with 65 sacks of cement. Plug down at 3:00 P. M., March 15, 1980.

TOPS: MISSISSIPPI - 2934'

Measurements taken from K. B.

CERTIFICATE

, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Blair #1, located on the 1113' SNL & 305' EWL NW/4 Section 32-19-1W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.


P. E. Plouffe, President