

KANSAS DRILLERS LOG

S. 33 T. 19 R. 1 W

API No. 15 — 113 — 20,606
County Number

Loc. 30' S of C SW NW SW
McPherson
County

Operator

Gould Oil, Inc.

Address 260 North Rock Road, Suite 210 Wichita, Kansas 67206


Well No. 1 Lease Name Nelson/Meyer

Footage Location 1020 feet from (N) (S) line 330 feet from (E) (W) line of SW/4

Principal Contractor Blackstone Drilling, Inc. Geologist Don Melland

Spud Date November 17, 1978 Total Depth 3068 P.B.T.D. 3054

Date Completed November 27, 1978 Oil Purchaser



Elev.: Gr. 1584

DF _____ KB 1589

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	28	172'	Common	100	3% Ca. Cl.
Production	7 7/8"	4 1/2"	10 1/2"	3066'	50/50 Pozmix	125	10% salt & 0.75 CFR-2 & 12 1/2# sx gilsonite

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	DP jets	2980-3000'

TUBING RECORD

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2250 gallons - 15% acid	2980'-3000'

INITIAL PRODUCTION

Date of first production 12/13/78	Producing method (flowing, pumping, gas lift, etc.) Flowing
DATE OF PRODUCTION PER 24 HOURS	Oil --- bbls. Gas 380 MCF Water trace bbls. Gas-oil ratio --- CFPB
Disposition of gas (vented, used on lease or sold) S.I.G.W.	Producing interval(s) 2980'-3000'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Gould Oil, Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Gas

Well No. 1 Lease Name Nelson/Meyer

33 T 19 R 1 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Lansing	2350	(-761)		
Mississippian	2961	(-1372)		
Cased hole GRN-CBL logs by Viking Services				
DST #1: 2935'-2980' (30"-45"-30"-45")				
GTS = 5 minutes				
Gauged 62 MCFD in 10" of first opening				
58 MCFD in 20"				
58 MCFD in 30"				
68 MCFD in 10" of second opening				
Stabilized throughout				
Rec: 50' Slightly GCM				
IFP = 45-34# ISIP = 545#				
FFP = 45-34# FSIP = 511#				
DST #2: 2982'-3003' (30"-45"-30"-45")				
GTS = 6 minutes				
Gauged 107 MCFD in 10" first opening				
138 MCFD in 20"				
181 MCFD in 30"				
215 MCFD in 10" second opening				
Stabilized throughout				
Rec. 50' slightly GCM				
IFP = 20-30" ISIP = 556#				
FFP = 56-45# FSIP = 545#				
DST #3: 3007'-3017' (30"-30"-30"-30")				
GTS = 47"				
Too small to measure				
Rec. 40' very slight Oil and GCM				
IFP = 11-22# ISIP = 488#				
FFP = 22-22# FSIP = 375#				
DST #4: 3018'-3036' (30"-30"-30"-30")				
Strong blow throughout				
Rec. 190' of Muddy Salt water				
IFP = 34-56# ISIP = 556#				
FFP = 79-102# FSIP = 545#				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Dale P. Jewett

Signature

Vice President

Title

April 20, 1979

Date