

35-19-1W



Blackstone Drilling, Inc.

Box 1194 • 523 West Kansas • Phone (316) 241-1250
 XX McPHERSON, KANSAS 67460

March 3, 1978

COMPANY: DECKER PETROLEUM INC.
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: D. BECKER #1
 LOCATION: SE SE SE Section 35-19-1W,
 McPherson, County, Kansas
 COMMENCED: February 24, 1978
 COMPLETED: March 2, 1978
 ELEVATION:

0	to	75	Clay
75	to	138	Blueshale
138	to	583	Shale
583	to	1180	Lime & Shale
1180	to	1595	Shale & Lime
1595	to	2330	Lime & Shale
2330	to	2822	Lime
2822	to	2886	Shale & Lime
2886	to	2980	Mississippi
		2980	T. D.

Cut 12 1/4" hole to 138' and run 140' of 8 5/8" surface casing, cemented with 100 sacks of cement at 138'. Plug down at 11:15 A. M., February 24, 1978. Cut 7 7/8" hole to 2980'. Run 2979.60' of 4 1/2" casing, cemented with 70 sacks of cement at 2978', 2 feet off bottom. Plug down at 1:00 P. M., March 2, 1978.

TOPS MISSISSIPPI - 2886'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your D. Becker #1, located on the SE SE SE. Section 35-19-1W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.