

15-113-20362
30-19-1W30-19-1W
NW/4**Blackstone Drilling, Inc.**

Box 455 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

June 22, 1976

COMPANY: PAUL BANDY

CONTRACTOR: BLACKSTONE DRILLING, INC.

FARM: ANDERSON A#2

LOCATION: 1400' EWL & 1160' NSL NW/4 30-19-1,
McPherson County, Kansas

COMMENCED: June 15, 1976

COMPLETED: June 21, 1976

ELEVATION:

0	to	40	Shale
40	to	80	Sand
80	to	200	Blue Shale
200	to	830	Shale & Lime
830	to	1110	Lime & Shale
1110	to	1570	Shale & Lime
1570	to	1980	Shale
1980	to	2175	Lime & Shale
2175	to	2390	Shale & Lime
2390	to	2696	Lime
2696	to	2820	Lime & Shale
2820	to	2931	Shale & Lime
2931	to	3155	Mississippi
3155	to	3413	Shale
		3413	T. D.

Cut 12 $\frac{1}{4}$ " hole to 200' and run 202' of 8 5/8" casing, cemented with 125 sacks of 2X Gel & 2X CG at 200'. Plug down at 12:30 P. M., June 15, 1976. Cut 7 7/8" hole to 3413'. Run 3417' of 5 $\frac{1}{2}$ " pipe, cemented with 100 sacks of cement at 3412 $\frac{1}{2}$ ". Plug down at 4:15, June 21, 1976.

TOPS: MISSISSIPPI - 2931' VIOLA - 3412 $\frac{1}{2}$ '

Measurements taken from K. B.

CERTIFICATE

I, F. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Anderson A#2, located on the 1400' EWL & 1160' NSL of NW/4, Section 30-19-1, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.