

MARATHON OIL COMPANY.
J.W. Whitright No. 3.

Plotted Texas CO
30-19-1W

SEC. 30 T. 19 R. 1W
C NL S $\frac{1}{2}$ SW $\frac{1}{4}$

*Plotted
Albert Wheeler*

total Depth. 2977.

County. McPherson


Comm. 5-5-36 Comp. 6-29-36

Hot or Treated.

Contractor.

Issued. 7-25-36

JUL 25 1936



CAS ING.	
20 "	89'
15 $\frac{1}{2}$ "	666'
12 $\frac{1}{2}$ "	1396'
10 "	2265'
8 5/8"	2611'
7 "	2942'

Elevation.

Production, Pot. 258 B.

Figures Indicate Bottom of Formations.

sand	80	slate	1090	shale	1885
shale blue	120	lime	1110	lime	1895
red rock	125	slate	1115	shale	1930
shale blue	165	lime	1120	lime	1950
red rock	170	shale	1130	sdv lime	1960
shale	190	lime	1160	3 BW 1950-60	
lime	195	shale	1165	lime	2030
4 BW 190-95		lime	1170	shale	2040
shale	345	shale	1175	lime	2085
lime	350	lime shells	1195	shale cave	2095
shale	370	slate dark	1220	lime	2105
lime	385	red rock	1230	shale	2115
shale	390	lime	1235	sand	2155
shale shells	410	shale	1260	HFV 2115-27	
shale	415	3 BW 1245-60		sdv lime	2170
lime	420	red rock	1265	sand	2210
shale	425	lime	1270	sand broken	2220
lime	435	slate	1290	shale	2260
shale	450	lime	1295	lime	2265
lime	470	shale	1310	red rock	2270
shale shells	495	lime shells shale		lime	2275
shale	510	black	1325	shale	2315
lime	535	slate	1330	lime	2580
shale	560	lime	1335	shale	2595
red rock	565	slate	1355	lime	2670
shale	570	red rock	1365	shale	2680
lime	605	shale	1400	lime	2690
shale	610	lime	1420	shale shells	2700
red rock	615	slate	1470	shale	2730
shale	620	lime	1490	lime	2735
lime	645	slate	1500	shale	2755
shale	648	lime	1505	lime	2765
lime	755	slate	1525	shale	2770
red rock	770	lime	1535	lime	2775
slate	815	shale	1540	shale	2780
sdv lime	845	lime	1545	lime	2790
shale dark	847	rod rock	1550	shale	2795
lime	865	lime	1560	lime	2805
slate	870	shale	1590	shale	2815
red rock	875	lime	1595	lime	2820
lime	900	slate	1650	var. col. shale	2840
slate	905	1 BW 1650-60		shale	2845
lime	915	lime	1670	lime	2855
slate	925	slate	1690	shale	2880
lime	945	lime	1700	var. col. shale	2911
shale	965	slate	1705	Top Chat 2911	
lime	975	lime	1715	chat	2977
shale	980	shale	1765	2930=2927 SLM	
shale shells	1020	lime shells	1780	2935=2947 SLM	
lime	1045	lime	1800	Total Depth	2977
slate	1055	shale	1805		
lime	1065	lime	1810	Pumped 118 barrels 24 hrs.	
slate	1070	shale	1830	natural.	
lime	1075	lime	1880	1000 gallons acid.	
				Pumped 258 barrels 24 hrs.	
				after acid.	