

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. SEc NW

Sec. 3 T.19 R. 10W

Casing Record.

County Rice.

10" 1835 Farn. Anton L. Zink No. 1
 20" 139'8 8 1/2" 2270 Company. Solar Oil Corp.
 15 1/2" 450 65/8" 3174 Contr. James Davis.
 12 3/8" 1212 53/16" 3281 Comm. 5-27-31 Comp. 7-8-31
 Total Depth. 3358 Shot Quarts Between.
 Correspondence Regarding This Well Should Be Referred To.



Figures Indicate Bottom of Formations.,
 Date Issued. 8-1-31

Elevation. 1733
 Initial Production. Dry

Formation	Depth	Formation	Depth	Formation	Depth.
cellar	10	red rock	1850	3 BW 2840-50 carrying 4 1/2 BW	2925
1 BW PHR 7'		lime	1885	shale	2928
sdv clay	22	slate	1890	lime	2940
water sand	25	lime	1895	shale	2960
sdv clay	30	slate	1925	lime sdv	2960
mud yellowhole cav.	90	lime	1975	light sh oil 2950-2955	
water sand	110	2BW 1950--60		lime	3030
HFV 90 to 110		slate	1990	showing oil 3015-3020	
mud blue	120	lime	1995	lime sdv	3035
shale blue	210	slate	2005	lime	3090
slate light	220	lime	2010	slate	3095
shale red	420	slate	2020	lime	3122
2 1/2 BW 220-230 5BW 305-10		lime	2045	red rock	3125
carrying 7 1/2 BW		slate & shells	2185	lime	3217
red rock	438	hole caving.		slate	3222
chalk	448	slate	2225	lime	3231
lime hydrate	460	lime	2240	conglomerate	3244
slate blue	465	slate	2250	lime	3250
red rock	550	lime	2255	conglomerate	3281
slate blue	565	slate	2260	reduced hole 3281 light show	
red rock	575	lime sdv	2270	oil 3275-3281 Cave	
red rock & gyp	700	6BW 2262-2270		conglomerate	3283
red rock	715	sdv shale	2305	sand	3286
slate & gyp	825	sdv lime	2320	very light show 3283-3286 little	
slate blue	910	1 1/2 Sec. BW 2305-2315		gas.	
slate and gyp	950	slate	2330	conglomerate	3304
gyp 1/2 BW 955	960	lime	2335	sand	3313
salt	1180	slate	2340	very light show at 3307.	
slate blue	1183	lime	2345	conglomerate	3328
salt	1195	slate	2350	chert	3332
slate and gyp	1400	lime	2370	light show oil 3329.	
red rock	1405	shale	2385	chert and green shale	3335
lime white	1415	lime	2390	siliceous lime	3358
slate	1420	shale	2425	3 BW 3354-7BW 3358. small show	
lime grey	1430	lime	2450	oil with water at 3354. hole	
slate and shells	1450	slate	2460	caving at 3358 green shale.	
red rock	1470	lime	2475	T.D. Plugged and Abd.,	
lime white	1525	slate	2485		
sdv lime	1585	lime	2490	8 1/2 UR from 2270 to 2550.	
water sand	1590	slate	2495		
2BW 1585-1590		sdv lime	2560		
lime sdv	1605	HFV 2495-2515			
1 BW 1590-1605 carrying 6BW		lime	2580		
lime	1623	slate	2587		
red rock	1630	lime	2665		
lime	1645	1/2 BW 2620-25			
slate	1650	slate	2670		
lime	1665	lime	2680		
slate	1670	slate	2683		
slate & lime shells	1695	lime	2695		
lime	1700	slate	2700		
slate	1705	lime sdv	2725		
red rock	1712	lime	2740		
lime	1725	slate	2742		
slate	1732	lime	2785		
red rock	1745	1 BW 2750-2755			
slate	1780	slate	2790		
lime	1795	lime	2810		
slate	1800	slate	2820		
lime	1810	lime	2830		
slate hole cav.	1825	slate	2840		
lime	1838	sdv shale	2850		
red rock					

2940
1733
1285

1733
438
+1295

3335
1733
1602

3332 set
1733
1599