

50035

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

C.H. WEAVER
Doran No. 1.

SEC. 13 T.19 R. 10W
NEc SE

Total Depth. 3310'


Comm. 7-29-36 Comp. 10-4-36

Shot or Treated.

Contractor. C.H. Weaver

Issued. 10-17-36

County. Rice



Elevation. 1757

CASING:

15 1/2" 170'
12 1/2" 425'
10 " 1703'
8 1/2" 2270'
6 5/8" 3265'
5 3/16 liner 60

Production. Pot. 194 B.

Figures Indicate Bottom of Formations.

sdv shale	10	red rock	1835	1/2 BWPH 2785
sand	55	lime	1865	small show oil 2980
water sand	115	shale blue & shells	1900	lime 3090
shale blue	145	shale grey	1930	shale black 3093
water sand	160	lime	1940	lime 3165
shale blue	220	Cave fr 1900-2200		shale grey 3170
red rock	410	shale grey	1955	lime 3190
chalk	417	lime	1995	shale 3194
lime	427	shale blue	2002	lime 3250
red rock	690	lime	2020	var. col. shales 3278
shale grey	745	shale	2050	conglomerate 3290
red rock	800	lime	2060	lime 3310
shale blue	865	shale blue	2080	Total Depth.
lime shells	875	lime	2095	
shale blue	905	shale	2110	
salt	1175	red rock	2115	Filled up 2100' of oil in
shale	1185	shale	2122	24 hours from 3306-3310
brkn lime	1245	lime	2140	
lime	1260	shale dark	2200	No correction in measurements
shale	1270	lime	2202	at 3265.
lime	1295	shale blue	2205	Was not treated with acid.
shale grey	1300	lime	2221	
lime	1305	shale blue	2230	
shale grey	1315	sdv shale	2270	
red rock	1320	HFH 2250-60		
lime	1330	lime	2272	
brkn lime	1370	shale	2276	
lime	1415	lime	2278	
shale	1425	shale blue	2325	
red rock	1435	lime	2330	
shale	1442	shale grey	2350	
lime	1465	lime	2360	
shale	1472	shale grey	2380	
lime	1515	lime	2390	
brkn lime	1525	shale grey	2425	
lime	1585	lime	2430	
36 W. FHR 1560-65		shale blue	2435	
shale grey	1590	lime	2485	
lime	1600	shale blue	2520	
shale blue	1610	lime	2775	
lime	1625	shale black	2780	
shale	1629	lime	2790	
lime	1652	shale dark	2805	
shale black	1658	lime	2815	

3291
1757
1534
2935
1757
1178
109