

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


ATLANTIC REFG.
Doran No. 2

DEEPENING RECORD

SEC. 13 T. 19 R. 10W.
CEL SE
1320' N. of SL
330' W of EL.

Total Depth 3307 FB 3295
Comm. 5-24-37 Comp. 7-27-37
Shot or Treated.
Contractor.
Issued. 8-24-39

County Rico.



CASING.

20" 86'
15 1/2" 157'
12 1/2" 710'
10" 1650'
8 1/4" 2245'
7" 3241'

Elevation. 1743

Production. Pot. 874 B.

Figures Indicate Bottom of Formations.

sdv shale	45	shale blue	1995
sand water	74	lime	1998
sand	86	shale	2034
clay yell w	125	lime	2050
sand HFW	150	shale blue	2075
shale blue	202	lime	2090
red rock	395	shale blue	2100
lime	412	red rock	2110
red rock	690	lime	2120
shale blue	740	shale blue	2160
red rock	795	shale blue	2198
shale blue	905	lime	2210
salt	1155	shale	2215
broken lime	1200	sdv shale	2245
red rock	1205	sand	2255
lime shells & shale	1250	shale blue	2262
shale grey & shells	1320	lime	2263
red rock	1325	shale blue	2265
broken lime	1365	lime	2295
shale grey	1380	shale grey	2305
lime	1400	lime	2320
shale grey	1405	shale	2325
broken lime	1425	shells & red rock	2340
red rock	1435	lime	2360
lime	1470	shale	2370
shale grey	1475	lime	2420
lime	1585	shale grey	2425
shale blue	1590	lime	2440
lime	1600	shale grey	2450
shale blue	1630	lime	2470
lime	1655	shale grey	2507
shale blue	1660	lime	2625
lime	1665	shale blue	2630
red rock	1675	lime	2650
lime	1680	shale grey	2655
shale blue	1695	lime	2787
red rock	1700	shale	2795
lime	1715	~~lime~~	2840
shale blue & shells	1727	shale grey	2920
red rock	1735	lime	2930
lime	1760	shale grey	2940
red rock	1765	red rock	2945
lime	1770	lime	3210
red rock	1775	shale	3215
lime	1810	lime	3248
red rock	1818	congl. cored	3248-3289
lime	1825	sil. limo cored	3289-3290
shale blue	1830	lime cored	3290-3299
lime	1840	lime	3301 1/2
shale blue & lime shells	1915	Total Depth.	
sdv lime	1925		
broken lime	1990		

DEEPENING RECORD

Comm. 9-8-37
Comp. 10-2-37
Production. Pot. 874 B.
Old T.D. 3301 1/2
white wtr sand 3301 1/2-3307
Plugged back to 3295'
Drilled to 3301
Total Depth.

511 3289
1743
-1546
Ls 2936 set
1743
-1193