


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

SHARON DRUG CO.
Nevius No. 1.

SEC. 21 T. 19 R. 10W
SWc NE

Total Depth. 3298'
Comm. 2-7-41 Comp. 3-12-41
Shot or Treated.
Contractor.
Issued. 4-19-41

County. Rice



CASING:
8" 115'
5" 3274'

Elevation. 1764

Production. Pot. 530 B. - Lansing
Pot. 103 B. - Arbuckle

Figures Indicate Bottom of Formations.

sand	75
shale & shells	115
shale	160
shale & red rock	315
red rock	435
anhydrite	460
shale	630
shale & shells	1100
salt lime & shale	1125
brkn lime & shale	1235
anhydrite & lime	1335
lime brkn	1425
shale sdy	1610
shale & lime shells	1815
lime brkn	2000
shale & lime	2060
shale	2230
shale lime shells	2295
shale	2350
shale shells	2420
shale	2450
lime brkn	2495
sand	2540
shale	2585
lime shells & shale	2655
lime	2790
shale & lime	2855
shale	2975
lime	3036
lime sft-S.oil	3039
lime sft cored	3056
lime sft	3062
lime	3165
shale & lime shells	3249
conglomerate & shale	3273
Arbuckle dolomite rot.	3275
Cable	
dolomite dense hrd	3289
dolomite (oil stained)	3294
dolomite dense	3296
Arbuckle chert	3298
Total Depth.	

2963
1764

-1199

3274
1764

-1510

At 3294 well made 1/3 BOPH
deepened to 3296 No increase
500 Acid thru csg
Made 2/3 BOPH
Deepened to 3298 (increase
oil)
1260' oil 4 1/2 hrs
Swabbed down & swabbed
between 8 & 9 BOPH for 12 H.
Potential 103 Bbls Pump from
Arbuckle.
Set Baker Packer 3248
Perforated 30 shots 3032-42
1300' oil 12 hrs
500 Gals. Acid
Potential from Lansing
530 B. Pmp