

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg., Wichita, Kansas.

STANOLIND OIL & GAS CO.
L. F. Manke No. 2.

SEC. 28 T. 19 R. 10W.
SE SW SE
330' N of S.L. 990' E of WL.

Total Depth. 3263 P.B. 3254
Comm. 7-6-37 Comp. 8-26-37
Shot or Treated 2000 gal.
Contractor.
Issued. 10-16-37

County Rice.



CASING.

103/4" 202'
6" 3247'

Elevation. 1771

Production. DRY

Figures Indicate Bottom of Formations.

sand	35
shale and shells	343
anhydrite	452
shale and shells	950
salt	1217
shale and shells	1250
broken lime	1417
broken lime & shale	1578
shale and shells	1707
broken lime	1732
shale and shells	2057
shale with stretches of lime	2154
shale and shells	2250
shale and shells	2359
broken lime and shale	2461
sticky shale and shells	2548
lime	2775
shale	2790
lime	2883
shale	2975
lime	3034
lime and shale	3121
lime	3179
shale and lime	3245

CORING RECORD.

Lansing lime	3247
dolomite dense	3248
dolomite porous	3249
dolomite dense	3250
dolomite porous With O.S.	3253
lime S.O. 700 ft oil in hole	3257
lime 1900' of oil in hole 300' of water	3266
Top of siliceous	3247
P.B.	3263
Cemented back to	3254
Temporarily plugged and abd.	

3247
1771
-1476

2548
1771
-777 TOP?