


SHELL PETROLEUM CORP.
 H. Rader No. 1

11-19-11
 SEC. 11 T. 19 R. 11W
 NE¹/₄ NE
 330' fr NL 330' fr EL NE¹/₄

Plotted Texas CO.
 County Barton.

Total Depth. 3392
 Comm. 9-1-36 Comp. 10- 5-36
 Shot or Treated. 1000 gal acid.
 Contractor.
 Issued. 10- 24-36

OCT 24 1936



CASING.

13" 252'

7" 3328'

Elevation.

Production. Pot. 358B.
 240 B.W. 22H.

Figures Indicate Bottom of Formations.

lime and sand	106	lime	2495	dolomite trace of	
shale and shells	125	shale and shells	2545	chert	3377
sand	135	broken lime & shale	2570	dolomite trace chert	
shale	147	lime	2585		3379
sand	160	shale and lime	2630	4 ¹ / ₂ B.O. 3 ¹ / ₂ Oil & Wtr.	
shale and shells	220	lime	2642	dolomite some shale	
sand shale&shells	252	lime	2841		3381 ¹ / ₂
red rock shale and shells	390	broken lime and shale		dolomite some shale	
red rock & shale	450	shale	2910		3387
broken lime	500	shale and lime	2990	dolomite green shale	
red rock shale and lime	680	shale	3015	and chert	3392
shale and lime	800	broken lime and shale	3028	Total Depth.	
shale and shells	1020	lime	3172		
salt	1275	lime	3211		
shale and lime	1338	lime light brown	3218		
shale and shells	1360	lime hard grayish			
broken lime	1400	brown	3223		
lime hard	1418	lime	3310		
broken lime	1450	conglomerate shale dark			
shale	1480	reddish brown some			
sdv lime	1500	light green	3315		
shale	1525	conglomerate sdv shale			
broken sdv lime	1550	dark reddish brown with			
shale	1570	lime pebbles	3320		
lime	1593	conglomerate shale			
shale	1630	reddish brown some			
broken lime & shale	1715	lime	3325		
lime	1745	conglomerate shale green			
broken lime	1778	and sand	3330		
lime	1788	dolomite and shale some			
shale and lime	1803	chert	3335		
broken lime and shale		3335 equals 3332 S.L.C.			
lime	1810	dolomite	3332		
shale	1825	dolomite	3333		
lime	1825	dolomite chert and			
red rock & shale	1835	shale pale green sdv	3336		
broken lime & shale	1880	dolomite chert shale pale			
broken lime	1920	green sdv	3338 ¹ / ₂		
shale	1960	dolomite small amount			
broken lime	1990	of shale	3341 ¹ / ₂		
shale and shells	2005	dolomite small amount of			
lime	2025	shale pale green sdv trace			
shale	2040	chert	3345		
broken lime	2070	chert some pyrite some			
shale & shells	2170	dolomite pale green			
lime	2180	shale	3346		
shale	2190	dolomite Rainbow show			
shale & shells	2250	oil in bailer	3347 ¹ / ₂		
lime	2270	dolomite	3353		
shale and shells	2325	dolomite	3363		
shale	2330	dolomite little chert and			
lime	2355	shale pale green	3365 ¹ / ₂		
shale	2390	dolomite some pale green			
lime	2410	shale	3367 ¹ / ₂		
shale and lime	2455	dolomite and chert	3374 ¹ / ₂		
shale	2470	dolomite little shale			
		pale green	3376		