

14-19-11W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - CHALMETTE PETRO. CORP.  
Farm - Eberhardt No. 2.

SEC. 14 T. 19 R. 11 W  
NW NE SE

Total Depth. 3345  
Comm. 12-15-45 Comp. 2-5-46  
Shot or Treated.  
Contractor.  
issued. 3-23-46

County. Barton  
KANSAS



CASING:  
8 5/8" 207'  
5" 3332'

Elevation. 1778

Production. Pot. 85 B Pmpg.

Figures Indicate Bottom of Formations.

sand & shale	0-135
shale	235
red bed shells	522
anhydrite	545
shale & shells	938
shale & salt	1107
salt shale	1200
shale & shells	1350
anhydrite	1399
shale	1469
lime & shale	1565
lime	1602
lime & shale strks	1650
shale	1695
cherty lime	1715
lime	1805
cherty lime	1814
lime & shale	2424
lime	2483
shale & lime	2665
lime	2835
lime & shale	2861
lime	2899
lime & sand	2915
lime	2935
lime & shale	2959
lime	2970
shale & lime	3030
lime	3042
shale	3050
lime	3337

Rotary T.D.  
dolomite 3345  
Total Depth

Geological Data

Tops:  
Anhydrite 522  
Brown Limestone 3038  
Lansing  
Limestone 3052  
S.O. 3081-85  
Arbuckle Dolo. 3330  
S.O. 3332-33  
Core 3333-37 rec.  
1' sat. dolo.

Testing Record:

DP bail 20' GPH  
500A bail 2' BOPH  
750A Swb. 2 1/2' BOPH