

14-19-11W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company - STANOLIND OIL & GAS CO.  
Farm - Eberhardt No. 2

SEC. 14 T. 19 R. 11W  
NW SE SE  
990' NSI, 990' WEL of Se/4

Total Depth. 3345  
Comm. 5-22-48 Comp. 6-20-48  
Shot or Treated.  
Contractor.  
Issued. 10-8-49

County. Barton  
KANSAS



CASING:  
10 3/4" 522' cem w/300 sx.  
7" 3310' cem w/250 sx.

Elevation. 1779 *ft*

Production. 60 bbls pr day.

Figures Indicate Bottom of Formations.

|                   |       |
|-------------------|-------|
| cellar            | 9 1/2 |
| sand              | 115   |
| shale, shells     | 210   |
| red rock, shells  | 243   |
| red bed           | 493   |
| anhydrite         | 516   |
| red rock, shale   | 695   |
| shale             | 814   |
| shale, shells     | 997   |
| salt, shale       | 1149  |
| shale             | 1319  |
| lime shells       | 1382  |
| lime brkn         | 1736  |
| lime              | 1841  |
| lime, shale       | 1900  |
| shale             | 1965  |
| lime brkn         | 2204  |
| shale             | 2290  |
| lime              | 2300  |
| shale             | 2328  |
| lime brkn         | 2398  |
| lime              | 2438  |
| lime w/shale brks | 2502  |
| lime              | 3005  |
| lime brkn         | 3120  |
| lime              | 3205  |
| shale             | 3221  |
| lime              | 3273  |
| shale             | 3279  |
| lime              | 3289  |
| dolomite          | 3294  |
| lime              | 3345  |
| Total depth       |       |

Tops:  
Arbuckle 3289

Oil or Gas Sands or Zones:  
Lansing 3033-3290  
Arbuckle 3310-3345