

24-19-11W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - VICKERS PETROLEUM CO., INC.
Farm - Herr "A" No. 44

SEC. 24 T. 19 R. 11 W
CEL SW NE

Total Depth. 3296
Comm. 11-26-45 Comp. 12-19-45
Shot or Treated.
Contractor. Acidize w/2000 gals.
issued. 1-5-46

County. Barton
KANSAS



CASING:
10 3/4" 173' Cem.
5 1/2" 3294' Cem.

Elevation. _____

Production. Swab 8 BPH

Figures indicate Bottom of Formations.

sand	0-73
shale & shells	220
red bed & shells	475
anhydrite	510
lime & shale	590
shale & shells	1010
salt shale & shells	1305
shale & shells	1440
shale & lime	1545
shale	1645
lime sdy	1680
lime brkn	1780
lime	1825
shale	1845
lime brkn	2085
shale & lime streak	2215
shale & shells	2325
shale & lime	2520
lime	2875
lime brkn	2950
lime & shale	3035
lime	3296
Total Depth	

Tops:

Lansing	3009
Base Kans. City	3250
Arbuckle	3294

Small show oil 3021- 25
Soft por., good show
oil, good odor 3096-3120
Fair por & fair
odor 3158-3161
Fair por & fair
odor 3196-3200
Fair por. & fair
show of oil 3221-3224

Fillup 1750' oil in 11
hrs @ 3295
Swab 6 BO
Drilled deeper one
foot, T.D. 3296
Swab 8 BOPH
Acidized w/2000 Gals.