


VICKERS PETRO.CO.  
Herr Est. "C" No. 1.

SEC.24 T.19 R. 11 W  
CNL NE SE

Total Depth. 3366'  
Comm. 10-14-41 Comp. 11-17-41  
Shot or Treated.  
Contractor.  
Issued. 12-6-41

County. Barton



CASING:  
10<sup>3</sup>/<sub>4</sub>" 182'6" Cem.  
5<sup>1</sup>/<sub>2</sub>" 3364' Cem.

Elevation.

Production. BHPot.3114 B.

Figures Indicate Bottom of Formations. less 7% Wtr  
Net Pot.2790 BO

surface	0-185
shale, shells, red bed	940
shale & salt	970
salt	1120
shale & shells	1280
anhydrite	1315
shale & shells	1595
sand	1635
shale & shells	1740
lime brkn	2025
shale & shells	2628
lime & shale	2665
lime	3270
lime & shale	3330
chat	3338
lime & shale	3351
lime	3366
Total Depth.	

Cemented 5<sup>1</sup>/<sub>2</sub>" csg  
RUST Set Lane Wells plug  
at 3157'  
Perforated csg 3094-3105 w/  
23 shots  
Top Lansing 3006  
Acidized 2000 Gals.  
Btm hole bomb potential 3114  
Bbls. less 7% wtr  
Net Pot. 2790 BOPD