

24-19-11W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


Company - VICKERS PETRO. CO., INC.  
Farm - Roth No. 2

SEC. 24 T. 19 R. 11W  
SE SW SW

Total Depth. 3384'  
Comm. 4-29-49 Comp. 5-15-49  
Shot or Treated.  
Contractor.  
Issued. 6-11-49

County. Barton

KANSAS



Elevation. 1770 *ft*

Production. Dry & Abandoned

Figures Indicate Bottom of Formations.

sand	80
clay yellow	120
shale & shells	183
pyrite, solid	187
shale & shells	210
red bed & red rock	395
red bed & shale	500
anhydrite	520
shale & shells	1015
salt & shale	1250
shale & salt	1300
lime brkn	1575
lime brkn, sand	1675
lime & sand	1700
lime	1925
lime & shale	2540
lime	2895
lime & shale	2940
shale & sand	3021
lime & shale	3034
lime	3291
shale & lime	3312
shale, sand, chert & pyrite	3353
dolomite RTD	3367
dolomite	3374
dolomite & shale	3384
Total Depth	

Tops:

Brown Lime	3021
Leasing	3034
96' break	3127-3145
Base Kansas City	3291
Detrital Zone (Conglo)	3312
Arbuckle	3353

No fluid any kind in hole  
 Perf. 11 shts. 3220-25, no show  
     12 shts. 3245-50, no show  
 Set Lane Wells plug at 3138'  
 Perf. 12 shts. 3125-36, no show  
     12 shts. 3137-48, some wtr, no oil  
     12 shts. 3127-33, no show fluid in zone  
 Fill up 500' wtr, 16 hrs. wtr coming from  
 3137-3148 zone.