


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

THREE-WAY DRLG.CO.
Shartz No. 1.

SEC.21 T.19 R.11 W
SE SE

Total Depth. 3382'
Comm. 6-28-43 Comp. 7-10-43
Shot or Treated.
Contractor. Three-Way Drlg.Co.
Issued. 7-24-43

County. Barton



CASING:
8 $\frac{1}{4}$ " 215'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

shale	20
sand	35
shale & shells	224
red rock	545
anhydrite	555
shale & shells	1080
salt	1220
shale & shells	1320
lime	1450
lime & shale	1645
lime	1700
lime cherty	1735
lime	1745
lime & shale brks	2017
shale & shells	2030
shale	2055
lime	2150
lime brkn	2200
lime	2250
shale & shells	2321
shale	2355
lime	2445
lime & shale brks	2520
shale	2553
lime & shale	2650
lime	2755
lime & shale	2825
lime	2927
shale & shells	2970
shale	3063
lime K. C.	3090
lime	3338
conglomerate shale	3352
lime	3382
Total Depth.	

Tops:
Brown Lime 3038
Iansing 3061
Shaly Conglomerate 3337
Arbuckle 3350

3081-84 porous, no stain or odor
3144-48 porous, slight oil stain
& faint oil odor
3152-72 good porosity, no oil
stain or odor
3352-53 slight porosity, slight
oil stain, no odor
3350-54 10% porosity, lgt stain
3371-76 good porosity, no oil
stain or odor
3373-82 good porosity, no show

All depths rig floor