


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

THE TEXAS CO.  
A. Henning No. 4.

SEC. 22 T. 19 R. 11W  
CE  $\frac{1}{2}$  NW NW

Total Depth. 3363'  
Comm. 7-24-41 Comp. 9-5-41  
Shot or Treated:  
Contractor. Helmerich & Payne, Inc.  
Issued. 10-4-41

County. Barton



CASING: Rotary O-3334  
Cable 3334-63  
10  $\frac{3}{4}$ " 253' Cem.  
7" 3141' Cem.  
5  $\frac{1}{2}$ " 3334' Cem.

Elevation.

Production. Pot. 53 B. Phy.  
No wtr

Figures Indicate Bottom of Formations.

|                     |      |
|---------------------|------|
| sand                | 100  |
| sand & shale        | 230  |
| shale               | 254  |
| red bed & shale     | 550  |
| sand & shale        | 570  |
| anhydrite           | 580  |
| red bed, salt & sh. | 1100 |
| shale               | 1280 |
| shale & shells      | 1500 |
| shale & lime shells | 1640 |
| lime brkn           | 1900 |
| shale & lime        | 2135 |
| shale               | 2273 |
| shale & lime        | 2660 |
| lime                | 2914 |
| lime & shale        | 2998 |
| shale               | 3042 |
| lime                | 3049 |
| shale               | 3065 |
| lime                | 3167 |
| wtr sand            | 3172 |
| lime                | 3184 |
| lime hrd            | 3188 |
| lime                | 3196 |
| shale               | 3201 |
| lime                | 3232 |
| lime brkn           | 3245 |
| lime                | 3326 |
| lime & shale        | 3334 |
| lime                | 3337 |
| lime hrd            | 3339 |
| lime                | 3363 |
| Total Depth.        |      |

Tops: Lansing 3055  
Pay 3141  
Arbuckle 3333

Acidized well w/500 Gals.  
Acid in Kansas City  
Acidized well w/5500 Gals.  
Acid in Arbuckle  
Physical potential 53 bbls  
oil and no wtr