

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

THE TEXAS CO.
Dena Zeigenbusch No. 2.

SEC. 23 T. 19 R. 11W
CS $\frac{1}{2}$ SW NE

Total Depth. 3428' PB 3190'
Comm. 6-15-41 Comp. 7-11-41
Shot or Treated.
Contractor. J.E. Trigg Drlg. Co.
Issued. 8-23-41

County. Barton

Rotary O-3350
Cable 3350-3428

CASING:
10 $\frac{5}{8}$ " 215' Cem.
7" 3350' Cem.



Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

surface	30
shale	490
shale & shells	525
lime	555
shale & shells	1265
lime	1340
shale & shells	1757
lime	1790
shale	1960
lime	2015
shale & shells	2127
shale	2440
shale & shells	2568
shale	2683
lime	2954
shale	3065
lime	3253
shale & shells	3299
lime	3343
conglomerate	3410
lime	3428
Total Depth.	

Plugged back from 3428 to 3260
Plugged back from 3260 to 3190

Perf. csg from 3089-93,
3132-70, 3206-10, 3240-48,
3307-11.

Tops: Lime 3049
K.C. lime 3064
Conglomerate 3344
Weathered Simpson 3363
Simp. 3370
Arbuckle 3418

Acidized w/ 1 - 150 gals.
1 - 150 gals.
1 - 500 gals.