


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

Company - C. E. ASH ET AL
Farm - Heinrich Roth "A" No. 5

SEC. 25 T. 19 R. 11W
CS $\frac{1}{2}$ SE NE

Total Depth. 3353'
Comm. 8-21-47 Comp. 10-20-47
Shot or Treated. Acid.
Contractor. C. E. Ash
Issued. 11-29-47

County. Barton
KANSAS



Elevation. _____

Production. Est. 50 bbls oil

CASING:

8-5/8" 210' LI
5-1/2" 3520' LI

Figures indicate Bottom of Formations.

clay	30
sand	50
shale	210
red rock	478
anhydrite lime	515
red rock & shale	915
salt	1075
shale	1310
lime	1615
shale & lime	2620
lime	2745
shale & lime	3323
lime	3353
Total Depth	

Tops:

Heebner Shale	2886
Brown Lime	3001
K.C. or White Lime	3021
Conglomerate	3307
Arbuckle	3318

Testing Kansas City. Plugged back to 3500' and shot 24 shots. 3264-76 Acid. 1000 and 3000 gals. No good. Plugged back to 3258'. 24 shots from 3224-32. Acid. w/1000 gals. No good. Shot 24 shots from 3232-40. Acid. w/3000 gals. Tested 1 $\frac{1}{4}$ BOFH. Plugged back to 3220'. Shot 24 shots from 3204-16. Acid. w/1000 and 3000 gal. Tested 1-3/4 BOFH. Drilled out plug at 3320'. Produced two pays. Together tested 3 BOFH.