


THE CROWN PETRO. THURMAN HILL & COMET DRIG CO. SEC. 25 T. 19 R. 11 W
Heinrich Roth No. 1. CNL NE NE

Total Depth. 3334
Comm. 12-13-41 Comp. 1-28-42
Shot or Treated.
Contractor. Comet Drig. Co.
Issued. 2-28-42

County Barton.



Rotary

CASING.

85/8" 202' left in
5 1/2" 3312' left in.

Elevation.

Production. Pot. 343 B.

Figures Indicate Bottom of Formations.

shale	27
sand	58
shale and shells	198
iron shell	203
shale and shells	215
red bed	480
anhydrite	504
shale and shells	995
salt	1265
shale and shells	1300
lime with shale brks	1455
lime	1477
shale	1490
lime	1535
lime and shale	1570
lime	1677
lime and shale	1727
lime	1985
lime and shale brks	2272
lime	2280
shale	2320
lime and shale	2432
shale	2455
lime	2485
sdv shale	2505
lime	2521
lime and shale	2650
lime	2932
lime and shale	2957
shale	3000
K.C. lime	3010
shale	3038
lime	3288
lime and shale	3313
Arbuckle lime	3334
Total Depth.	

1st pay 3319-23
2nd pay 3326-32